The PE endorsement includes the installation and abandonment activities for this project. The PE endorsement does not include any requalification or uprate activities for the project. Requalification or uprate actives and buffer zone documentation related to the project will be endorsed later under a separate seal:



**PROJECT ID 22-92164 ECKERT ST REPLACEMENT** 

Base mapping provided by 3rd party Engineering Firm. The facilities shown on the plan must be field verified and their location is not part of the PE Seal. Utilize 811 and exposures when paralleling and crossing facilities.

# **INSTALLATION ORDER NUMBER** ABANDONMENT ORDER NUMBER 22-0229441-00 (LP) ABANDONMENT ORDER NUMBER **R-2334 RETIREMENT (584)**

22-0229440-00 23-0221225-00(MP)

23-0221465-00

**SANDS AVE REQUAL (0001) CREEK REQUAL (0001) NEELY ST REQUAL (0001)** 

23-0221422-00 23-0221464-00 23-0221463-00

### PROJECT INFORMATION

FIELD ENGINEER/TECHNICIAN: SHIVRON SUGRIM CONSTRUCTION FLL: WILLIAM TOTTEN

BELE ACRES BORO / LEET TWP PERMITS: STATE PERMIT - SR 4036

ENVIRONMENTAL PERMIT THE VALLEY-ROCHESTER/2231

ALLEGHENY (003) COUNTY:

TAX DISTRICT/TOWNSHIP ID: 0030218, 0030291, 0070412, 0070478 MAP/GRID NUMBER: 7564492K, 7564492L, 7564492O, 7564492P


24 HR, EMERGENCY LINE: 1-888-460-4332

VALVE NO.	FACUITY		VALVE INSERTED?		DISPOSITION			
		LOCATION DESCRIPTION			WANTED	MAN MAN META	VALVE REMARKS IN PLACE BUT I UD	NCC WHITEN
			YES*	NO	BOX.	LID REMOVED	FLMCMLD	CO-COUR
		NONE						
,								
,								

PHOPOSED FACILITIES - SYS	TEM MOP AND PRESSURE TEST DATA
SYSTEM NUMBER	37022480
SYSTEM NAME	HIDDEN VALLEY-BELL ACRES LP
SYSTEM MOP (PSIG)	LP
SEGMENT MAOP (PSIG)	60
MINIMUM TEST PRESSURE (PSIG)	90
MAXIMUM TEST PRESSURE (PSIG)	125

PROPOSED FACILITIES - SYS	TEM MOP AND PRESSURE TEST DATA
SYSTEM NUMBER	37022357
SYSTEM NAME	AMBRIDGE - BADEN MP
SYSTEM MOP (PSIG)	47
SEGMENT MAOP (PSIG)	60
MINIMUM TEST PRESSURE (PSIG)	90
MAXIMUM TEST PRESSURE (PSIG)	125

# **JOB TYPE: AGE & CONDITION (557/558) VICINITY MAP**



## PROJECT DESCRIPTION

CPA TO INSTALL MEDIUM PRESSURE GAS MAIN. LP SYSTEM AND SINGLE FEED REGULATOR TO BE ABANDONED, CUSTOMERS TO BE TIED OVER TO MP SYSTEM. TOTAL OF --2,771FT OF PL TO BE REQUALIFIED

NOTE: BELL ACRES: FOLLOW ORDINANCE NO. 324. BOROUGH REQUIRES FULL ROADWAY WIDTH RESTORATION UNLESS OTHERWISE AGREED UPON BY BELL ACRES AND BOROUGH ENGINEER AFTER INPSECTION, MILL AND OVERLAY WITH 1.5 INCH. WEARING COURSE REQUIRED.

## **SHEET INDEX**

DWG.	DESCRIPTION
T-1	TITLE SHEET
GN-1	GENERAL NOTES
BOM-1	BILL OF MATERIALS
0-1	TIE IN OVERVIEW SHEET
0-2	REQUALIFICATION OVERVIEW SHEET
L-1 - L-5	LAYOUT PLANS
D-1 - D-4	CONSTRUCTION DETAILS / REQUAL PREPARATION STEPS
ISO	R-2334 ISOMETRIC
BUFFER 1&2	REQUAL BUFFER ZONE DRAWINGS

## **PROJECT SUMMARY TABLE**

PROPO	SED INS	STALLATION		PAC	POSED ABA	NDONMENT
LENGTH (FT)	SIZE (	IN) TYPE	Ш	NGTH (FT)	SIZE (IN	) TYPE
3,958	4*	PMMF	-	99'	2"	BSLP
1,390'	2	PMMF	,	587	3"	BSLP
				3,876	4"	BSLP
				206	2	PLP
				466'	4"	PLP
				2		UNK
5,348	TOTAL	INSTALLATION (FEE	n	5,236	TOTALA	BANDONMENT (FEET)
	-	PROPOSI	ED GAS	SERVI	CES	
		REPLACEMENTS	TIE O	VERS	TOTAL SERVICE	ES METER OUTS
ESTIMATED GAS SERVICES		83	0		83	21

MATERIAL APPROVED FOR USE ON THIS JOB ORDER IS LIMITED TO WHAT IS LISTED IN THE BILL OF MATERIALS

ANY ADDITIONAL MATERIAL MUST BE APPROVED FOR USE BY THE P.E. RESPONSIBLE FOR THIS PROJECT.





Call before you dig. CALL TOLL-FREE 1-800-242-1776 PA ONE-CALL DESIGN REQ SN#

20231042913 - ECONOMY BORO 20231042912 - BELLE ACRES BORO PRELIMINARY - 14 APRIL 2023

### **PROPOSED**

		REVISION	8			
0	XXX	ISSUED FOR	CONSTRU	CTION		
REV. #	DATE	Di	DESCRIPTION			
DESIGNED IN	Shir	ron Sugrim	0/1/23	412415-87		
DRAWN BY		P. CORSOLINI				
CHECKED BY			-			
AS-BUILT BY						
100000		RAME	DATE	PHONE		

INST# 22-0229440-00 ABAN# 22-0229441-00 PROJECT ID# 22-92164 2231- ECKERT - REPL JO AMBRIDGE, ALLEGHENY (003)

DRAWING TITLE:

TITLE SHEET

DRAWING NO:

T-1

TCC/LOA: